

Noise barrier L-00163 and L-00164, Aarau

Aarau · 2020

SERVICE AREA

Demolition work, bored piles, base wall, foundation work, surfacing work

PROJECT OVERVIEW

Replacement noise barriers along T5 Aaretalstrasse, over a length of approx. 410 m. Dam dismantling and demolition of existing foundations. Create bored piles and base wall. Dam, shoulder and road maintenance work.

Main quantities

1,500 m³ of excavation and fill, 1,500 tons of excavated and inert material transported away, 435 m of cased bored piles DN 700 mm / 410 m base wall created civil engineering, road construction and noise protection

